



INSTALL 3" WEEP HOLES AT BOTTOM OF TRENCH WITH 1/4" GALVANIZED SCREEN OVER UPSTREAM END.

NOTES:

1. CONCRETE ANCHOR WALLS (CLASS 3000) SHALL BE CONSTRUCTED USING FORMS WHEN SEWERS, STORM DRAINS, AND OTHER PIPELINES ARE CONSTRUCTED WITH SLOPES 20% OR GREATER. REMOVE FORMS PRIOR TO BACKFILLING TRENCH.

2. SPACING OF OF ANCHOR WALLS SHALL BE:	<u>SLOPE</u>	<u>SPACING</u>
	20-34%	35 FEET
	35-50%	25 FEET
	50+ %	15 FEET OR CONCRETE ENCASEMENT

**City of
McMinnville**

PIPE ANCHOR DETAIL

DATE: AUGUST 2022

DRAWING NO. 30